

PROJECT: Houston Medical Center Expansion

ADDENDUM NO. 1

DATE: June 15, 2026

ARCHITECT: Healthcare Design Partners

ENGINEER: XYZ Engineering Consultants

BID DATE: July 15, 2026

GENERAL

This Addendum forms a part of the Contract Documents and modifies the original Bid Documents dated June 1, 2026.

All bidders shall acknowledge receipt of this Addendum in their proposal.

MECHANICAL REVISIONS

Item M-1

Reference: Mechanical Schedule M601

Cooling Tower CT-2

REVISE:

Cooling Capacity: 1,000 Tons

TO:

Cooling Capacity: 1,250 Tons

Reason: Updated building cooling load calculations.

Item M-2

Reference: Section 23 65 00 Cooling Towers

ADD:

Cooling towers shall include factory-installed conductivity controller for automated bleed control.

Item M-3

Reference: Section 23 65 00 Cooling Towers

REVISE:

Maximum Sound Level: 80 dBA at 50 feet

TO:

Maximum Sound Level: 75 dBA at 50 feet

Item M-4

Reference: Approved Manufacturers

ADD:

Approved Manufacturers:

Marley BAC Evapco

No additional manufacturers are approved by this addendum.

Item M-5

Reference: Startup Requirements

ADD:

Manufacturer representative shall be present during initial startup and owner training.

END OF ADDENDUM NO. 1