

PROJECT: Houston Medical Center Expansion

SHEET: M601

COOLING TOWER SCHEDULE

Equipment Tag: CT-1

Description: Factory-Assembled Induced Draft Counterflow Cooling Tower

Service: Condenser Water Heat Rejection

Cooling Capacity: 1,250 Tons

Flow Rate: 3,000 GPM

Entering Water Temperature: 95°F

Leaving Water Temperature: 85°F

Design Wet Bulb Temperature: 78°F

Fan Motor: 30 HP

Power Requirements: 480V / 3PH / 60Hz

Maximum Sound Level: 75 dBA at 50 Feet

Approved Manufacturers: Marley BAC Evapco

Required Accessories: VFD Basin Sweeper Piping Ladder and Safety Cage Vibration Switch Electric Basin Heater

Notes: 1. Cooling tower shall be CTI certified. 2. Cooling tower shall be rated in accordance with CTI Standard 201. 3. Tower shall withstand 130 MPH wind loading. 4. Tower shall include drift eliminators with maximum drift rate of 0.0005%. 5. Tower shall be suitable for outdoor installation in Houston, Texas.

Equipment Tag: CT-2

Description: Factory-Assembled Induced Draft Counterflow Cooling Tower

Service: Condenser Water Heat Rejection

Cooling Capacity: 1,250 Tons

Flow Rate: 3,000 GPM

Entering Water Temperature: 95°F

Leaving Water Temperature: 85°F

Design Wet Bulb Temperature: 78°F

Fan Motor: 30 HP

Power Requirements: 480V / 3PH / 60Hz

Maximum Sound Level: 75 dBA at 50 Feet

Approved Manufacturers: Marley BAC Evapco

Required Accessories: VFD Basin Sweeper Piping Ladder and Safety Cage Vibration Switch Electric Basin Heater

Notes: 1. Cooling tower shall be CTI certified. 2. Cooling tower shall be rated in accordance with CTI Standard 201. 3. Tower shall withstand 130 MPH wind loading. 4. Tower shall include drift eliminators with maximum drift rate of 0.0005%. 5. Tower shall be suitable for outdoor installation in Houston, Texas.