

SNS Cooling Solutions

PROPOSAL NO: P-2026-00124

DATE: June 25, 2026

TO: ABC Mechanical Contractors

PROJECT: Houston Medical Center Expansion

PROJECT LOCATION: Houston, Texas

SUBJECT: Cooling Tower Equipment Proposal

Dear ABC Mechanical Contractors,

Thank you for the opportunity to provide this proposal for the Houston Medical Center Expansion project.

SNS Cooling Solutions is pleased to offer the following cooling tower equipment in accordance with the project requirements, specifications, schedules, and addenda.

PROPOSED EQUIPMENT

Quantity: 2

Manufacturer: Marley

Model: NC8414

Description: Factory-Assembled Induced Draft Counterflow Cooling Tower

Included Accessories:

• Variable Frequency Drive Package • Basin Heater • Basin Sweeper Piping • Conductivity Controller • Vibration Switch • Access Ladder • Safety Cage • Quiet Fan Package

PERFORMANCE SUMMARY

Flow: 3,000 GPM

Entering Water Temperature: 95°F

Leaving Water Temperature: 85°F

Design Wet Bulb: 78°F

Sound Level: 74 dBA @ 50 Feet

Certification: CTI Certified

PRICING

Equipment: \$270,000

Accessories: \$33,600

Total Proposal Price: \$357,034

NOTES

1. Proposal based upon Contract Documents and Addendum No. 1.
2. Pricing valid for 30 days.
3. Equipment selection based upon Marley Selection Software output.
4. Startup assistance included.
5. Freight excluded unless specifically noted.

EXCLUSIONS

1. Installation labor.
2. Structural steel supports.
3. Electrical installation.
4. Controls integration beyond factory-supplied equipment.

Thank you for the opportunity to provide this proposal.

Respectfully,

SNS Cooling Solutions Sales Engineering Department